

PERFORMANCE RESULTS

Otto Graf GmbH
Carl-Zeiss-Straße 2-6, 79331 Teningen
Germany

10 weeks nominal loading test
Typ of the tank: Graf Carat S

Graf ANAEROBIX septic tank
Combination of sedimentation and filtration process

Nominal organic daily load	0.24	kg/d		
Nominal hydraulic daily load	0.60	m ³ /d		
Material	polypropylene			
Treatment efficiency (nominal sequence)		Efficiency	Effluent	
	BOD ₅	51.2 %	184 mg/l	
	SS	85.0 %	53 mg/l	
Electrical consumption	0.00	kWh/d		

Performance tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH
(PIA GmbH)
Hergenrather Weg 30
D-52074 Aachen

Certified according to
ISO 9001:2008



Notified Body number: 1739



This document replaces neither the declaration
of conformity nor the CE marking.



Prüfinstitut für Abwassertechnik GmbH
geprüft - tested - teste

Elmar Lancé

January 2012